

## APPROXIMATE MATERIALS COSTINGS IN EUROS

(Bought 2009 and 2010)

These prices are approximate in some cases, you should carefully price everything before commencing!

ITEM	QUANTITY	EURO	NOTES
Concrete	pads	900	
Feet		200	
Fixings (bat metalworks)		400	
Timber		2,700	
Panelvent	60 no.	1,197	
18mmPlyt&g	46 sheets	644	
Plasterboard	80 @ 8.70	696	
Solitex	172 sq.m	291	3 rolls
intello plus	172 sq.m	468	3 rolls
Floor insulation	45 sq.m	1567	Rockwool
Roof insulation	68 sq.m	1,400	BioBased 501
Walls insulation	109 sq.m	2,200	BioBased 501
Floor insulation support	15 sheets	150	hardboard
Extra racking	10 sheets	100	9mm OSB
Onduline	200 sq.m	1600	2 x 0.85 cover @ €8
Trims		800	
Sanitary ware		1000	
Electrical		2000	
Plumbing		2000	
Glass for large windows		1000	
Windows		2000	
Kitchen		1,500	
Screws, nails etc		800	
TOTAL		€25,613	

Panelvent racking, Solitex breather membrane and Intello airtightness membrane were purchased from McCann and Byrne, Athboy, Co. Meath 046-9432104

BioBased 501 open cell insulation was supplied and fitted by Econstruction, Rathcoole, Co. Dublin 01 2987155

Onduline corrugated cladding and roofing Was supplied by Irish Insulations Ltd, Dublin