

ERECTING THE FRAME

YOU NOW HAVE THE FRAMES STACKED AND READY TO GO.

TO ERECT THE FRAME YOU WILL NEED:

- 1 THE DIFFERENT TIMBER ELEMENTS NEATLY STACKED AND READY TO USE
 - 2 SUITABLE NAILS AND SCREWS FOR FIXING THE ELEMENTS TOGETHER
 - 3 A GROUP OF HELDERS - ABOUT SIX IS A GOOD NUMBER. THEY NEED TO BE PROPERLY BRIEFED AND WEARING HARD HATS. SOME WITH EXPERIENCE IS GOOD!
 - 4 ENOUGH EQUIPMENT TO GO AROUND - HAMMERS MOSTLY!
 - 5 ROPES FOR HAULING UP THE FRAMES AND LONG (4m+) TIMBERS FOR TEMPORARILY SECURING THE FRAMES AS YOU GO.
 - 6 SOME PLYWOOD FOR TEMPORARY FLOORING PLUS SOME SCAFFOLDING PLANKS.
- THIS PART OF THE BUILDING PROCESS REQUIRES ABOUT THREE DAYS AND IS BEST DONE IN GOOD WEATHER.

OK! LETS GO.....!